

JAI NARAIN VYAS UNIVERSITY, JODHPUR

No. JNVU/FE/CC/18/3888

Dated :28-05-2018

Quotations for **42U Floor standing Server Rack with installation in University**

Due Date : 04-06-2018


Dear Sir,

You are requested to quote for the material as per list enclosed/as noted on reverse specifying delivery period. The quotations must be sent in sealed covers by registered post or be placed in the tender box kept for the purpose or handed over personally in the office or undersigned duly super scribed '**Quotations For 42U Floor standing Server Rack with installation in University**

Due Date : 04-06-2018 and addressed to the undersigned.

1. The quotations must reach this office not later than 4.p.m. on the due date.
2. The prices should be quoted in Indian currency for the latest models available, giving detailed specifications with appropriate literature in English or Hindi from the manufacturers concerned. The prices should be (a) F.O.R. JODHPUR inclusive of customs/excise duty, packing, forwarding freight, insurance and other incidental charges in case of outside firms (b) FREE DELIVERY at the Departmental Stores in case of local firms. Sales tax should be mentioned separately,
3. The power supply available at Jodhpur is (a) 220 volts, single phase, 50 cycles (b) 440 volts, three phase, 50 cycles, The electrically driven equipments should confirm to the above specifications,
4. In case of foreign import you will be required to submit, duly completed with G.I.F. values, seven copies of each of (a) Import License applications (b) 'Not manufactured in India' certificate (c) 'Custom Duty Exemption' certificate.
5. The payment for the items ordered for would be made after the articles have been received and found in order.
6. All legal proceedings, if necessity arises to institute any, by any of the parties concerned, shall be lodged in courts situated at Jodhpur and not elsewhere.
7. The documents will not be entertained through a bank or any other source, unless specifically agreed to by us,
8. We are not bound to accept the lowest tender and may reject any tender or any part of the tender without assigning any reason thereof.
9. The renderers will have to submit the latest income-tax and sales-tax clearance certificates without which the tenders are liable to be rejected.
10. Earnest money @ 2% of the approximate cost of tender amounting to App. Cost Rs. 98,000/- should be deposited in cash with cashier of this office or by Demand Draft/Fixed Deposit receipt in name of the Jai Narain Vyas University, Jodhpur, without which the tender may not be accepted.
11. Detailed specification alongwith manufacturer's name together with a sample (where applicable) should be given.
12. The rates with be valid upto :- 30-11-2018
13. The tenders with be opened on :- 07-06-2018

Yours faithfully,


DIRECTOR
COMPUTER CENTRE
JAI NARAIN VYAS UNIVERSITY
JODHPUR


2.

Quotation Date : 28-05-2018
 Last Date : 04-06-2018
 Opening Date : 07-06-2018
 Valid upto : 30-11-2018

Annexure – A.

S No.	Parameter	Item Specification	Qty.
1	42U Floor Standing Server Rack with installation as per University requirement		1
	Type	19" 42U rack mounted on the floor Floor Standing Server Rack - 42U with Heavy Duty Frame for rigidity. Top cover with FHU provision. Top & Bottom cover with cable entry gland plates. Heavy Duty Top and Bottom frame of MS. Two pairs of 19" mounting angles with 'U' marking. Depth support channels - 3 pairs with an overall weight carrying Capacity of 600Kgs. All racks should have mounting hardware 2 Packs, Blanking Panel. Stationery Shelf (2 sets per Rack) All racks must be lockable on all sides with key for each rack Racks should have Rear Cable Management channels, Roof and base cable access	
	Wire Managers	One Vertical and Two Horizontal.	
	Power Distribution Units	Power Distribution Unit - Vertically Mounted, 32AMPS with 12 Power Outputs. of 5/15 Amp Sockets), Electronically controlled circuits for Surge & Spike protection, , 32AMPS MCB,	
	Doors	The racks must have steel (solid / grill / mesh) front / rear doors and side panels. Racks should NOT have glass doors / panels. Front and Back doors should be perforated with at least 63% or higher perforations. Both the front and rear doors should be designed with quick release hinges allowing for quick and easy detachment without the use of tools.	
	Fans and Fan Tray	Fan 90CFM 230V AC, 4" dia (4 Nos. per Rack) Fan Housing Unit 4 Fan Position (Top Mounted) (1 no. per Rack) - Monitored - Thermostat based - The Fans should switch on based on the Temperature within the rack. The temperature setting should be factory settable. This unit should also include - humidity & temperature sensor	
	Metal	Sheet Steel Profile	
Side Panel	Detachable side panels (set of 2 per Rack)		
2	Fully loaded 24Port Fiber LIU Rack-Mountable including 24 multimode pigtail adopter and splicing tray with installation, this shall be replaced from existing LIU to NEW LIU.		3
3	Fiber Splicing Charges		72
4	Multimode SC-LC Duplex Patch Cord		12

1. Payment after satisfactory installation
2. Delivery : F.O.R our stores
3. Warranty one year


DIRECTOR
COMPUTER CENTRE
AI NARAYAN VYAS UNIVERSITY
JODHPUR